BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT31100/CALL-4

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/15/2019-20, Date: 01.10.2019

Improvements to roads and drains at Badrappa layout and surrounding area in ward no. 08 Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SAMBASHIVA REDDY C ( )		
				In Figures		In Words
1	125.82	Removing & Refixing stone slabs of drains and pointing in C.M.(1:3)	Cum	73.1	9197.44	Rupees Seventy Three and Ten Paise Only
2	461.34	KSRB 2-2.2:Earthwork excavation for foundtion of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary Soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications	Cum	78.87	36385.89	Rupees Seventy Eight and Eighty Seven Paise Only
3	76.89	KSRB 4-1.3:Providing and layingi n position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth including cost of all materials, labour, HOM of machienry, curing complete as per specifications.	Cum	4681.81	359984.37	Rupees Four Thousand Six Hundred Eighty One and Eighty One Paise Only
4	146.79	KSRB 4.2.2:Providing andlaying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs, with 20mm and down size graded granite metal coarse aggregates @0.878 cum and fine aggregates @ 0.459 cum, with superplastisiser @ 3lts confirming to IS 9103-1999 Reaffirmed - 2008, machine mixed, concrete laid in layres not exceeding 15 cms, thick vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase,lintles, retaining walls, return walls, walls (any thickness) includng attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills fillets etc, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5890.58	864678.24	Rupees Five Thousand Eight Hundred Ninety and Fifty Eight Paise Only
5	7.34	KSRB 4.9-1:Providing T.M.T Steel reinforcement for RCC Work including straightening, cutting, bending hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wasstge shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Tonne	58300.9	427928.61	Rupees Fifty Eight Thousand Three Hundred and Ninety Paise Only
6	1118.4	KSRB 4-6.4:Providing and removing centering, shuttering, strutting proppoing etc, and removal of formwork for Vertical surface such as walls at any thickness including attached pilasters butresses, plinth and string courses cost of all materials, labour complete as per specifications.	Sqm	281.85	315221.04	Rupees Two Hundred Eighty One and Eighty Five Paise Only
7	293.58	Providing granite Slabs of Selected quality roughly dressed and fixed in cement mortor (1:6) including fixing curing etc,. Complete. 10cms thick	Sqm	749.35	219994.17	Rupees Seven Hundred Forty Nine and Thirty
8	2328	Providing chamfering edges to stone slab 2.5 cms. Wide as per specifications. (only chamfered length shall be recorded	Nos	33.66	78360.48	Rupees Thirty Three and Sixty Six Paise Only
9	1000	5.29(b) Providing and fixing Pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with toop and bottom wideth 114 and 165 mm respectively 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, includng form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unoading lead and lift transportatin etc, complete.	Nos	301.09	301090.00	Rupees Three Hundred One and Nine Paise Only

C. Sambashiva Reddy
Signature of the contractor

26/12
Executive Engineer
26/12

...o.	Approved Qty.	Description	Unit	Approved Tender Rates of SAMBASHIVA REDDY C ( )		
				In Figures		In Words
10	180	KSRRB 15-19.1:Providing and applying ready mix priming coat over concrete/ masonry/asbestos cement sheet/ plastered surfaces including preparing the surface after thoroughly cleaning of oil grease, dirt and other foreign matter, and sand preparing including cost of materials, labour complete as per specifications.	Sqm	25.01	4501.80	Rupees Twenty Five and One Paise Only
11	180	KSRRB 15-20.1:Providing and applying floor painting with redy mix paint in two coats (excluding priming coat) on new concret / asbestos cement sheet / plastered surfaces brushing to give an even shade qafter preparing the surface after throughly cleaning oil, diert, dust other foreign matter and sand preparing including cost of materials, labour, complete as per specifications.	Sqm	48.09	8656.20	Rupees Forty Eight and Nine Paise Only
12	461.34	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/sand/.kanker/moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specification	Cum	96.19	44376.29	Rupees Ninety Six and Nineteen Paise Only

C. Sambashiva Reddy
Signature of the Contractor

26/12
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

26/12